

**City of Riveria Beach**  
**CDBG FY 19-20 PROJECT 26TH COURT FROM AVENUE M TO 27TH STREET**  
**BID No. 986-20-1**  
**EXHIBIT B**

Item No.	Description	Quantity		Unit Price	Total
		Total	Unit		
				\$	\$
<b>Overhead Items</b>					
1	Bonds and Insurance	1	LS		
2	Mobilization	1	LS		
3	Maintenance of Traffic	1	LS		
4	Permit Fees	1	AL	\$15,000.00	\$15,000.00
5	Professional Audio/Visual of Construction Site	1	LS		
6	Project Identification Sign	2	EA		
7	Survey and Record Drawings (Layout/As Builts)	1	LS		
<b>SUBTOTAL OVERHEAD ITEMS:</b>					\$
<b>Proposed Roadway and Sidewalk</b>					
8	Remove Existing Sidewalk (4-inch)	511	SY		
9	Remove Existing Driveway Apron and Sidewalk (6-inch)	77	SY		
10	Remove Existing Driveway Apron (Asphalt)	283	SY		
11	Remove Existing Driveway - Private Property Contingency	300	SY		
12	Construct Concrete ADA Curb Ramp (Various Configurations)	2	EA		
13	Construct Concrete Sidewalk (4-inch)	711	SY		
14	Construct Concrete Driveway Apron (6-inch)	405	SY		
15	Construct Concrete Driveway - Private Property Contingency (6-inch)	30	SY		
16	Construct F Curb and Gutter	1324	LF		
17	Mill and Resurface Existing Asphalt (1-inch)	689	SY		
18	Furnish and Install St. Augustine Sod	970	SY		
19	Furnish and Install Traffic Sign and Posts	8	EA		
20	Construct Stamped Concrete Speed Hump	1	EA		
<b>SUBTOTAL PROPOSED ROADWAY AND SIDEWALK ITEMS:</b>					\$
<b>Proposed Pavement Marking</b>					
21	Furnish and Install 24" White Stop Bar	12	LF		
22	Furnish and Install 12" White Exterior Crosswalk Stripes	122	LF		
23	Furnish and Install 6" Solid Double Yellow Stripes w/RPM	380	LF		
24	Furnish and Install 6" Solid Yellow 10-30 Skip w/RPM	90	LF		
25	Furnish and Install 6" Solid White Edge Lines	114	LF		
26	Furnish and Install Solid White Striping for Speed Hump	2	EA		
<b>SUBTOTAL PROPOSED PAVEMENT MARKING ITEMS:</b>					\$
<b>Proposed Drainage</b>					
27	Furnish and Install Type C Curb Inlet and Grate	1	EA		
28	Furnish and Install 48" Diameter Curb Inlet	2	EA		
29	Furnish and Install Inlet Pollution Retardant Baffles/Weir	2	EA		
30	Furnish and Install 18" RCP Storm Drain	50	LF		
31	Furnish and Install 18" RCP Storm Drain w/ Exfiltration Trench	20	LF		
<b>SUBTOTAL PROPOSED DRAINAGE ITEMS:</b>					\$
<b>Proposed Water Main and Sanitary Sewer Line</b>					
32	Grout and Abandon Existing 4-inch ACP WM	828	LF		
33	Furnish and Install Water Main (6-inch, PVC)	785	LF		
34	Pavement Restoration	1430	SY		
35	Furnish and Install 8" CIP Sewer Lining	1032	LF		
36	Contingency/Allowance for 8" VCP Sewer Repairs	50	LF		
37	Gravity Sanitary Sewer Manhole Rehabilitation	4	EA		
38	Install sewer lateral and clean out - single, long side	3	EA		
39	Install sewer lateral and clean out - single, short side	3	EA		
40	Install sewer later and clean-outs - double, long side	4	EA		
41	Install sewer lateral and clean out - double, short side	3	EA		
42	Furnish and Install 1" PE Single Water Service	2	EA		
43	Furnish and Install 1" PE Single Water Service	3	EA		
44	Furnish and Install 2" Double Water Service	3	EA		
45	Furnish and Install 2" Double Water Service	4	EA		
46	Furnish and Install DIP Pressure Main Fittings (6-inch)	0.30	TN		
47	Furnish and Install Gate Valves	2	EA		
48	Connect to Existing Water Main	3	EA		
49	Furnish and Install 6" line stops	2	EA		
50	Furnish and Install Sample Points	2	EA		
<b>SUBTOTAL PROPOSED WATER MAIN AND SANITARY SEWER ITEMS:</b>					\$
<b>TOTAL BID</b>				\$	